

LIMESCAPES GUIDE **FOR EXPOSED CONCRETE OR Poured LIMESTONE**

1. Preparation of Quote - either onsite visit or from site plans provided.
2. Acceptance of Quote.
3. Job commencement date confirmed by contractors. Final layout to be discussed.
4. Site Preparation - by client or Limescapes. Pedestrian area at 75mm thickness.
Trafficable area at 100mm thickness.
5. Installation of Formwork to define the areas to be poured. Mesh installed if required.
6. Concrete delivered and installed.
7. Exposed Concrete retardant applied, then washed back to expose the decorative aggregate.
Poured Limestone textured and pattern installed.
8. Control Cuts installed into the concrete/limestone to control cracking.
9. Acid Wash or wash down in preparation for Sealing.
10. Sealing - can only be installed after a minimum of 24 hrs for limestone and
7-14 days for Exposed Concrete (pending weather conditions).

“We recommend that a sealer coat be applied to all our products to enhance and protect their appearances. The use of aftermarket sealers is not recommended and may be detrimental to the visual look and appearance of your premium paving alternative.”

Finally,

- a. No foot traffic to the installed product for 24 hrs.
- b. No heavy traffic (cars) for 7-10 days.
- c. After sealing, please keep off the product for minimum of 24 hrs.

We here at Limescapes hope you enjoy the visual and practical benefits of the premium paving selection we offer. No doubt your choice will enhance your property for many years to come.

Note: Whilst we take the necessary precautions to control cracking by way of preparation, finishing off and installing control cuts, some minor hairline cracks may occur over the course of the products lifetime due to the nature of the product.

50B KING EDWARD ROAD
OSBORNE PARK WA 6017

PO BOX 1071
OSBORNE PARK WA 6916

T: 9445 8333

F: 9445 8311

E: info@limescapes.com
www.limescapes.com

ABN: 48 348 376 175